

Interconnection System Impact Study Report Request # GI-2007-11

CTG #'s 5 & 6 (269 MW total - summer) Additions at Fort St. Vrain Generation Plant in Summer 2009

PSCo Transmission Planning March 4, 2008

Executive Summary

On or about October 24, 2007 Public Service Company of Colorado (PSCo) Transmission Planning received a generation interconnection request to perform an Interconnection System Impact Study (SIS, or "Study") to assess the impact of interconnecting two simple-cycle gas-fired combustion turbine generators (CTG 5 & CTG 6) at its Fort St. Vrain (FSV) generation plant located north of Denver in Weld County, Colorado. Based upon information provided by the Customer (PSCo - Energy Supply Function), the total net output of the two General Electric CTGs is 269 MW (summer net) / 331 MW (winter net), with a planned back-feed date of January 15, 2009, and a commercial operation in-service date of no later than May 31, 2009. This Study was performed for the summer 2009 (269 MW total) ratings, and included shortcircuit and dynamic stability studies. The details of these studies are identified in the Dynamic Stability Analysis Study Results section of this report. Steady-state power flow studies were not performed in this SIS, as these were performed for a 300 MW total, 2009 summer case in the previous Special Study (NQ-2007-2, final report issued 10/24/07). Additional steady-state power flow studies based upon a winter peak load (2009-2010) for a 331 MW CTG5 - CTG6 output will be performed separately, and a separate study report will be issued once this study is completed.

This study also determined the scope of work and costs associated with the installation and interconnection of the two new generator step-up transformers (GSU, one each per CTG 5 & 6) into the existing 230 kV switchyard at FSV, and has identified additional transmission network upgrades and costs that were not identified in the initial NQ-2007-2 study. The upgrades include replacing seventeen 230 kV breakers in the FSV switchyard, due to the increased level of maximum 230 kV short-circuit levels associated with the added generation at FSV, and a required relocation of the two 230 kV cap banks at FSV. The details of these upgrades are identified in the <u>Cost</u> <u>Summaries and Details</u> section of this report.

Based upon the investigations completed, the required transmission interconnections and network upgrades (except all FSV breaker replacements) should be achievable by the summer of 2009. The work required consists of:



 Upgrades Required for Interconnection (FSV): Install two new 230 kV, 2breaker bays and associated relaying, and metering at FSV, to provide 230 kV interconnection facilities for the two new main GSU transformers for the CTG5 & CTG6. Includes costs associated with re-locating one of two existing 230 kV capacitor banks.

Network Upgrades Required for Delivery:

- FSV: replace seventeen 230 kV breakers due to increased short-circuit interrupting duty requirements (completed in 2009 – 6/2010, but do not impede 5/31/09 Commercial Operation Date).
- Replace the conductor on a 2.5-mile section of the Ft. Lupton FSV 230 kV double circuit line.
- Minor line termination upgrades (conductor jumpers, relay settings changes, etc.), or utilize the 4-hr. emergency ratings capability of existing bus conductor at six substations.
- Expedite from May 2010 to May 2009 the previously approved and budgeted project to install a second 230/115 kV, 280 MVA autotransformer at Valmont Substation.

Total Project Cost for Interconnection & Network Upgrades for Delivery: \$7.568 million (plus \$4.7 million separately budgeted, but expedited Valmont 230-115 kV, 280 MVA Autotransformer #2 installation).

Dynamics Stability Analysis Study Results (performed by Siemens / PTI)

Input Data

The benchmark stability analysis started from a WECC approved 2011HS1BP power flow base case, with the associated machine model data for the 2011 summer peak period. This case has been successfully used in recent stability analyses for several other generator system impact studies. The case was further modified with the topology and load data imported from a recent 2009 heavy summer peak load "PSCo budget case", for the PSCo (control area 70) and WAPA (control area 73). A second power flow case was created that added the two combustion turbines (CTG5 & CTG6, 135 MW / 206 MVA ea.), along with their respective main 230-18 kV, 200 MVA GSU transformers, to the benchmark power flow case. Generation from the new units was assumed to displace generation from the existing Comanche units. The machine models for the two new units were based on test results for similar units at FSV (e.g., CTG4), as the specific manufacturer (GE) data was not made available at the time the study was begun. The Customer provided the actual GE



machine data after the studies were completed. This new data was compared to the typical model data, and was determined to have insignificant differences with the typical machine model data used in the study. The test results were also used to update the machine dynamics models for the existing combustion turbines.

Methodology

The stability analysis was performed using PSS[™]E version 30.2. After reviewing the data for reasonableness and obtaining a flat start with the benchmark case, dynamic simulations were performed for both the benchmark case and the case with the new FSV CTG5 & CTG6 generators (GI-2007-11) for a common set of system disturbances to determine if the addition of the new FSV generation would have any adverse impacts on the system.

Rotor angles, mechanical and electrical power, generator terminal voltages, and frequency were monitored for representative generating units throughout control areas 70 and 73. In addition, voltages at the 115-, 230-, and 345-kV buses in areas 70 and 73 were also monitored.

WECC planning criteria including voltage deviation criteria for system response after disturbances was used in the analysis. Specifically, WECC requires that for a single contingency, transient voltage dips cannot exceed 25% at load buses, or 30% at non-load buses, cannot exceed 20% for more than 20 cycles at any load bus, cannot have a post-transient voltage deviation exceed 5% at any bus, and the frequency cannot dip below 59.6 Hz for 6 cycles or more at a load bus. For multiple contingencies, transient voltage dips cannot exceed 30% at any bus and cannot exceed 20% for more than 40 cycles at any load bus, cannot have a post-transient voltage dips cannot exceed 30% at any bus and cannot exceed 20% for more than 40 cycles at any load bus, cannot have a post-transient voltage dips cannot exceed 30% at any bus and cannot exceed 20% for more than 40 cycles at any load bus, cannot have a post-transient voltage deviation exceed 10% at any bus, and frequency cannot dip below 59.0 Hz for 6 cycles or more at a load bus. The addition of any new generation cannot produce system performance that is out of compliance with the values stated above.

Contingencies Studied

A list of faults near the proposed GI-2007-11 project were developed that should provide a reasonably thorough evaluation of system performance (see Table 1). Twelve three-phase faults on single 230-kV circuits were studied, with fault clearing in 5 cycles. In addition, four three-phase faults were studied that required the tripping of two circuits in 5 cycles. Finally three contingencies were studied that consisted of single-line-to-ground faults with delayed clearing, at 23 cycles.

Results

For all contingencies that were studied, the results of the stability analysis indicates that the addition of GI-2007-11 (FSV CTG5 and CTG6) does not have an adverse



impact on the response of the system to severe system disturbances. All generation remained on line, except where disconnected from the system. All oscillations were positively damped and voltage deviations on nearby 115 kV and 230 kV buses were well within criteria. The contingencies consisting of delayed clearing were similarly behaved with no undamped oscillations and voltage response within criteria as well. Results of system behavior in the benchmark case were similar to those observed for the case with GI-2007-11 generation.



]	Fault	-			Cle	eared Circu	iit 1		Cleared Circuit 2 (N - 2 and Breaker Failure)							
1	Locatio	n	Duration		Bus 1			Bus 2		Circuit		Bus 1			Bus 2		Ckt
Name	kV	Number	(Cycles)	Name	kV	Number	Name	kV	Number	Circuit	Name	kV	Number	Name	kV	Number	
St.Vrain	230	70410	5	St.Vrain	230	70410	FtLupton	230	70192	1				None			
St.Vrain	230	70410	5	St.Vrain	230	70410	Isabelle	230	70544	1				None			
St.Vrain	230	70410	5	St.Vrain	230	70410	Weld PS	230	70471	1				None			
St.Vrain	230	70410	5	St.Vrain	230	70410	Fordham	230	73562	1				None			
St.Vrain	230	70410	5	St.Vrain	230	70410	GreenVal	230	70048	1				None			
St.Vrain	230	70410	5	St.Vrain	230	70410	LongPeak	230	73116	1				None			
St.Vrain	230	70410	5	St.Vrain	230	70410	Spndle	230	70592	1				None			
St.Vrain	230	70410	5	St.Vrain	230	70410	Windsor	230	70474	1				None			
FtLupton	230	70192	5	St.Vrain	230	70410	FtLupton	230	70192	1				None			
Spndle	230	70592	5	St.Vrain	230	70410	Spndle	230	70592	1				None			
Niwot	230	70297	5	Isabelle	230	70544	Niwot	230	70297	1				None			
St.Vrain	230	70410	5	St.Vrain	230	70410	Spndle	230	70592	1	St.Vrain	230	70410	Isabelle	230	70544	1
St.Vrain	230	70410	5	St.Vrain	230	70410	GreenVal	230	70048	1	Keenesbg	230	70820	GreenVal	230	70048	1
St.Vrain	230	70410	5	St.Vrain	230	70410	FtLupton	230	70192	1	St.Vrain	230	70410	FtLupton	230	70192	2
St.Vrain	230	70410	5	St.Vrain	230	70410	Isabelle	230	70544	1	Spndle	230	70592	Valmont	230	70447	1
St.Vrain	230	70410	23	St.Vrain	230	70410	LongPeak	230	73116	1	St.Vrain	230	70410	Isabelle	230	70544	1
St.Vrain	230	70410	23	St.Vrain	230	70410	Weld PS	230	70471	1	St.Vrain	230	70410	Fordham	230	73562	1
St.Vrain	230	70410	23	St.Vrain	230	70410	Windsor	230	70474	1	St.Vrain	230	70410	Fordham	230	73562	1

Table 1: List of Bus Faults Used in Dynamics Study

Note: If the N - 2 breaker failure simulations meet criteria with a clearing time of 23 cycles, no further simulations for that scenario will be run. If the N - 2 simulations do not meet criteria with a clearing time of 23 cycles, the critical clearing time for that scenario will be determined.



Cost Summaries and Details

The following is a summary of the interconnection costs and network upgrades required to connect two new simple-cycle gas-fired combustion turbine generators (CTG5 and CTG6, each rated approximately 135MW (summer) / 206 MVA) into the PSCo transmission system at the Fort Saint Vrain 230 kV switchyard. The scope of the interconnection facilities and network upgrades were identified in Non-Queued Study Report labeled NQ-2007-2 provided by PSCo Transmission System Planning on October 19, 2007.

Facility	Description	Cost
Fort Saint Vrain 230kV Switching Station	 Interconnection Facilities funded by TAM: Expand two 230kV buses to the east Install two 230kV bays in the Breaker & Half, one interconnection point per bay Four 230kV circuit breakers Ten 230kV gang switches Associated foundations, structures, and yard work 	\$2,461,836
Fort Saint Vrain 230kV Switching Station	 Network Upgrades funded by TAM: Replace 17 230kV circuit breakers due to insufficient fault duty 	\$3,692,890
Fort Saint Vrain 230kV Switching Station	 Operations and Maintenance Costs funded by TAM: Relocate 50MVAR capacitor bank to the west of current position 	\$28,194
Fort Saint Vrain 230kV Switching Station	 Interconnection Costs funded by Customer: Metering instrument transformers (set of three per interconnection) Two dead-end towers Metering panel equipment Associated foundations, structures, and buswork 	\$594,321
Fort Saint Vrain Generating Plant	 LF/AGC Costs funded by Customer: Load control RTU All required cabinets, wiring, and associated controls equipment 	\$123,280
Ft. Lupton – Ft. St. Vrain 230kV Lines 5311, 5329	Network Upgrade funded by TAM: Reconductor 15 spans (2.5 miles) of existing double- circuit 230kV transmission line • 1033.5 Ortolan conductor (540 MVA)	\$621,946



Facility	Description	Cost
Cherokee Substation	Network Upgrade funded by TAM: Upgrade line termination jumpers on Cherokee - Lacombe 230kV Ckt #5057	\$15,000
Hogback Substation	 Network Upgrades funded by TAM: Upgrade line termination jumpers on Hogback – Lookout 115kV Ckt #9794 Upgrade line termination jumpers on Hogback – Soda Lakes 115kV Ckt #9794 	\$30,000
	Total Interconnection Costs by TAM	\$2,461,836
	Total Network Upgrades by TAM	\$4,359,836
	Total Operations & Maintenance Costs by TAM	\$28,194
	Total Interconnection Costs funded by Customer	\$717,601
Total	Total cost of GI-2007-11 (Not including previously funded Valmont Autos)	\$7,567,467
Time Frame	See Schedule – Figure 2	

230kV Bus Fault Current Ratings – Fort Saint Vrain Switching Station

The 230kV bus fault currents at the Fort Saint Vrain switching station, with the addition of the new CTG5 & CTG6 generation, are as follows:

Single-line to Ground Fault: ~40,783A < -85.7 deg 3-Phase Fault: ~38,949A < -86.1 deg

GI-2007-11 Ft. St. Vrain Generation Addition Assumptions

- The cost estimates provided are "scoping estimates" with an accuracy of +/-30%.
- All applicable overheads are included. AFUDC has been excluded.
- There is no contingency added to the estimates.
- All estimates are in 2008 dollars.
- No overtime is included in the labor estimates.
- PSCo (or its contractor) crews will perform all construction and wiring associated with PSCo-owned and maintained equipment.
- No siting or permitting work will be required.
- A Certificate of Public Convenience and Necessity (CPCN) will be required from Colorado Public Utility Commission (CPUC) for the PSCo generation addition (GT5 & GT6, NQ-2007-2 / GI-2007-11) project, and has already been filed, with CPUC ruling expected by 4/1/08.



- Spare fiber optics between plant and switchyard.
- All required transmission outages necessary to support construction would be obtained as needed.
- Assumes a dedicated construction force to the project (in-house crews).
- Construction of new substation facilities is within existing property boundaries.
- Back-feed date of new generation is 1/15/2009. Interconnection facilities must be complete by this date.
- Commercial date of new generation is 5/31/2009. All network upgrades other than the 17 breaker replacements must be complete by this date. Breaker numbers requiring replacement:
 - 5316, 5318, 5300, 5301, 5303, 5304, 5308, 5311, 5312, 5315, 5319, 5322, 5323, 5324, 5325, 5327, 5329.
- Breaker replacements are anticipated to be complete by 2nd quarter, 2010.



Figure 1: Fort St.Vrain Budget One-Line Diagram

(Note – additions for new GTG5 & GTG6 GSU's interconnection equipment shown dashed)






Figure 2: Fort St.Vrain Preliminary / Draft Schedule

ID	Task Name	Duration	Start	Finish		0000											0040			
0	(and a sector 10.70)				Nov	2008 Jan	Mar	May	Jul	Sep 1	lov Ja	Jan Mar May Ju			Sep	Nov	2010	2010 Jan Mar		
1	GI-2007-11 FT ST VRAIN G5 & G6 ADDITIONS	328 days?	Wed 2/27/08	Fri 5/29/09	NOV	Jell	IVIEI	ividy	JUI	oeh 11	SL NU	IVIa	n May	Jul	Seb	NUV	Jan	IVIal	Ma	
2	FT ST VRAIN SWITCHYARD INTERCONNECTION	231 days?		Wed 1/14/09			~				~									
3	Add Two 230kV Bays	the local data and the second	Wed 2/27/08	Wed 1/14/09							~									
4	Substation Engineering & Design	64 days?	Wed 2/27/08	Mon 5/26/08	1		-													
5	Material Procurement	130 days?	Mon 3/3/08	Fri 8/29/08				_												
		the second se		Wed 12/31/08	1		-													
	Substation Construction	173 days?	1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1	The second second second second	1						_									
7	Commissioning/Testing	44 days?	Fri 11/14/08	Wed 1/14/09	1					-		HE								
8	FSV G5 & G6 BACKFEED	0 days	Thu 1/15/09	Thu 1/15/09	1							1/15	hr							
9	FT ST VRAIN NETWORK UPGRADES	281 days?	Mon 3/3/08	Mon 3/30/09								_								
10	FSV-Ft Lupton Lines 5311, 5329 Reconductor	185 days?	Mon 3/3/08	Fri 11/14/08			^	- 21		<u>^</u>										
11	Transmission Engineering	65 days?	Mon 3/3/08	Fri 5/30/08	1															
12	Material Procurement	110 days?	Wed 4/30/08	Tue 9/30/08	1															
13 🔳	Transmission Construction	33 days?	Wed 10/1/08	Fri 11/14/08																
14	Cherokee Substation Jumper Upgrades	130 days?	Mon 9/1/08	Fri 2/27/09	1															
15 🔳	Substation Engineering	22 days?	Mon 9/1/08	Tue 9/30/08					2.5											
16	Material Procurement	86 days?	Mon 9/22/08	Mon 1/19/09						1										
17	Substation Construction	20 days?	Mon 2/2/09	Fri 2/27/09	1							1000								
18	Hobgack Substation Jumper Upgrades		Mon 9/22/08	Mon 3/30/09						<u> </u>		~								
19 🔳	Substation Engineering	23 days?	and the second se	Fri 10/31/08								-								
20	Material Procurement	86 days?	Mon 9/22/08	Mon 1/19/09	1					_										
21	Substation Construction	21 days?	Mon 3/2/09	Mon 3/30/09	1															
	FT ST VRAIN CUSTOMER LF/AGC - TESTING	and the second second	Mon 6/2/08	Fri 5/29/09																
22		260 days?		and the second s																
23	Substation Engineering	44 days?	Mon 6/2/08	Thu 7/31/08	1			_												
24	Material Procurement	87 days?	Fri 6/27/08	A DISAL AND A DUTATION DOCTOR	1					_										
25	LF/AGC Installation	54 days?	Mon 11/3/08	Thu 1/15/09	1															
26 🔳	Plant Testing	106 days?	Fri 1/2/09	Fri 5/29/09																
27	FSV PLANT COMMERCIAL DATE	0 days	Mon 6/1/09	Mon 6/1/09			1000							6/1						
28	FSV BREAKER REPLACEMENTS	543 days?	Mon 3/3/08	Wed 3/31/10														\sim		
29	Substation Engineering	109 days?	Tue 7/1/08	Fri 11/28/08																
30	Material Procurement	226 days?	Mon 3/3/08	Mon 1/12/09																
31	Substation Construction	313 days?	Mon 1/19/09	Wed 3/31/10	1															
hoject: Sched late: Wed 2/2		Progress Milestone	8		Summary Project Sur	nmary			nal Tasks nal Milestone	8	_	Deadline	D							