

Provisional Interconnection Study Report for PI-2024-12

11/11/2024



Table of Contents

| | | |
|------|--|----|
| 1.0 | Executive Summary..... | 4 |
| 2.0 | Introduction..... | 5 |
| 3.0 | Study Scope | 7 |
| 3.1 | Steady State Criteria..... | 7 |
| 3.2 | Transient Stability Criteria | 8 |
| 3.3 | Breaker Duty Analysis Criteria..... | 8 |
| 3.4 | Study Methodology | 9 |
| 3.5 | Contingency Analysis | 9 |
| 3.6 | Study Area..... | 10 |
| 4.0 | Base Case Modeling Assumptions..... | 11 |
| 4.1 | Benchmark Case Modeling | 11 |
| 4.2 | Study Case Modeling | 12 |
| 4.3 | Short-Circuit Modeling..... | 12 |
| 5.0 | Provisional Interconnection Service Analysis | 14 |
| 5.1 | Voltage and Reactive Power Capability Evaluation..... | 14 |
| 5.2 | Steady State Analysis..... | 17 |
| 5.3 | Transient Stability Results | 21 |
| 5.4 | Short-Circuit and Breaker Duty Analysis Results | 23 |
| 5.5 | Affected Systems..... | 23 |
| 5.6 | Summary of Provisional Interconnection Analysis..... | 23 |
| 6.0 | Cost Estimates..... | 24 |
| 6.1 | Schedule..... | 26 |
| 7.0 | Summary of Provisional Interconnection Service Analysis..... | 28 |
| 8.0 | Contingent Facilities | 29 |
| 9.0 | Preliminary One-Line Diagram and General Arrangement for PI-2024-12..... | 30 |
| 10.0 | Appendices | 32 |

List of Figures

| | |
|--|----|
| Figure 1: Point of Interconnection of PI-2024-12 | 6 |
| Figure 2: Preliminary One-Line of PI-2024-12 at the Goose Creek 345 kV switching station..... | 30 |
| Figure 3: Preliminary General Arrangement for PI-2024-12 at the Goose Creek 345 kV switching station | 31 |

List of Tables

| | |
|---|----|
| Table 1 – Transient Stability Contingencies..... | 9 |
| Table 2 – Generation Dispatch Used to Create the Eastern Colorado Benchmark Case (MW is Gross Capacity) | 11 |
| Table 3 – Reactive Capability Evaluation for PI-2024-12 | 16 |
| Table 4 – Generation Dispatch to Resolve the Diverged P1 Contingency | 17 |
| Table 5 – East Pocket - Single Contingency Overloads | 18 |
| Table 6 – East Pocket - Multiple Contingency Overloads..... | 19 |
| Table 7 – Diverged P7 Contingencies | 20 |
| Table 8 – Transient Stability Analysis Results | 22 |
| Table 9 – Short-Circuit Parameters at PI-2024-12 POI (Goose Creek 345 kV switching station) | 23 |
| Table 10 – Transmission Provider’s Interconnection Facilities | 24 |
| Table 11 – Station Network Upgrades | 25 |
| Table 12 – Proposed Milestones for PI-2024-12 | 26 |

1.0 Executive Summary

The PI-2024-12 project is a Provisional Interconnection Service request for a 438 MW Wind Generating Facility with a Point of Interconnection (POI) at the Goose Creek 345 kV switching station. PI-2024-12 is the Provisional Interconnection Service request associated with Generation Interconnection Request 5RSC-2024-16 in the 5RSC cluster.

The total estimated cost of the transmission system improvements required for PI-2024-12 to qualify for Provisional Interconnection Service is \$8.822 million (Table 10 and Table 11).

The initial maximum permissible output of PI-2024-12 Generating Facility is 438 MW. The maximum permissible output of the Generating Facility in the PLGIA¹ will be reviewed quarterly and updated, if there are changes to the system conditions assumed in this analysis, to determine the maximum permissible output.

Security: PI-2024-12 is a request for Energy Resource Interconnection Service (ERIS). For ERIS requests, security shall estimate the risk associated with the Network Upgrades and the Interconnection Facilities and is assumed to be a minimum of \$5 million.

In addition, the Interconnection Customer would assume all risk and liabilities with respect to changes between the PLGIA and the LGIA², including changes in output limits and Interconnection Facilities, Network Upgrades, Distribution Upgrades, and/or System Protection Facilities cost responsibility.

The Provisional Interconnection Service in and of itself does not convey transmission service.

¹ Provisional Large Generator Interconnection Agreement (PLGIA): Shall mean the interconnection agreement for Provisional Interconnection Service established between Transmission Provider and/or the Transmission Owner and the Interconnection Customer. The pro forma agreement is provided in Appendix 8 and takes the form of the Large Generator Interconnection Agreement, modified for provisional purposes.

² Large Generator Interconnection Agreement (LGIA): Shall mean the form of interconnection agreement applicable to an Interconnection Request pertaining to a Large Generating Facility that is included in the Transmission Provider's Tariff.

2.0 Introduction

PI-2024-12 is the Provisional Interconnection Service³ request for a 438 MW Wind Generating Facility located in Cheyenne County, Colorado.

- The POI of this project the new Goose Creek 345 kV switching station. The Goose Creek 345 kV switching station is part of the Colorado's Power Pathway project.
- The Commercial Operation Date (COD) to be studied for PI-2024-12 as noted on the Provisional request form is 3/16/2026.

The geographical location of the transmission system near the POI is shown in Figure 1. Note an approximation was used to overlay the new Colorado's Power Pathway onto the current one-line diagram.

³ **Provisional Interconnection Service** shall mean an Interconnection Service provided by Transmission Provider associated with interconnecting the Interconnection Customer's Generating Facility to Transmission Provider's Transmission System and enabling that Transmission System to receive electric energy and capacity from the Generating Facility at the Point of Interconnection, pursuant to the terms of the Provisional Large Generator Interconnection Agreement and, if applicable, the Tariff.




Figure 1: Point of Interconnection of PI-2024-12

3.0 Study Scope

The purpose of this study is to determine the impacts to the PSCo system and the Affected Systems from interconnecting PI-2024-12 for Provisional Interconnection Service. Consistent with the assumption in the study agreement, PI-2024-12 selected Energy Resource Interconnection Service (ERIS)⁴.

The scope of this report includes voltage and reactive capability evaluation, steady state (thermal and voltage) analysis, transient stability analysis, short-circuit analysis, and cost estimates for Interconnection Facilities and Station Network Upgrades. The study also identifies the estimated Security⁵ and Contingent Facilities associated with the Provisional Interconnection Service.

3.1 Steady State Criteria

The following Criteria are used for the reliability analysis of the PSCo system and Affected Systems:

P0—System Intact conditions:

Thermal Loading: $\leq 100\%$ of the normal facility rating

Voltage range: 0.95 to 1.05 per unit

P1 & P2-1—Single Contingencies:

Thermal Loading: $\leq 100\%$ Normal facility rating

Voltage range: 0.90 to 1.10 per unit

Voltage deviation: $\leq 8\%$ of pre-contingency voltage

P2 (except P2-1), P4, P5 & P7—Multiple Contingencies:

Thermal Loading: $\leq 100\%$ Emergency facility rating

Voltage range: 0.90 to 1.10 per unit

Voltage deviation: $\leq 8\%$ of pre-contingency voltage

⁴ **Energy Resource Interconnection Service** shall mean an Interconnection Service that allows the Interconnection Customer to connect its Generating Facility to the Transmission Provider's Transmission system to be eligible to deliver the Generating Facility's electric output using the existing firm and non-firm capabilities of the Transmission Provider's Transmission System on an as available basis.

⁵ **Security** estimates the risk associated with the Network Upgrades and Interconnection Facilities that could be identified in the corresponding LGIA.

3.2 Transient Stability Criteria

The transient voltage stability criteria are as follows:

- a. Following fault clearing, the voltage shall recover to 80% of the pre-contingency voltage within 20 seconds of the initiating event for all P1 through P7 events for each applicable Bulk Electric System (BES) bus serving load.
- b. Following fault clearing and voltage recovery above 80%, voltage at each applicable BES bus serving load shall neither dip below 70% of pre-contingency voltage for more than 30 cycles nor remain below 80% of pre-contingency voltage for more than two seconds, for all P1 through P7 events.
- c. For Contingencies without a fault (P2.1 category event), voltage dips at each applicable BES bus serving load shall neither dip below 70% of pre-contingency voltage for more than 30 cycles nor remain below 80% of pre-contingency voltage for more than two seconds.

The transient angular stability criteria are as follows:

- a. P1—No generating unit shall pull out of synchronism. A generator being disconnected from the system by fault clearing action or by a special Protection System is not considered an angular instability.
- b. P2–P7—One or more generators may pull out of synchronism, provided the resulting apparent impedance swings shall not result in the tripping of any other generation facilities.
- c. P1–P7—The relative rotor angle (power) oscillations are characterized by positive damping (i.e., amplitude reduction of successive peaks) > 5% within 30 seconds.

•

3.3 Breaker Duty Analysis Criteria

Fault Current after PI addition should not exceed 100% of the Breaker Duty rating. PSCo can only perform breaker duty analysis on the PSCo system. Before the PI goes in-service the Affected Systems may choose to perform a breaker duty analysis to identify breaker duty violations on their system.

3.4 Study Methodology

For PSCo and non-PSCo facilities, thermal violations attributed to the request include all new facility overloads with a thermal loading >100% and increased by 1% or more from the benchmark case overload post the Generator Interconnection Request (GIR) addition.

The voltage violations assigned to the request include new voltage violations which resulted in a further variation of 0.01 per unit.

Since the request is for Provisional Service, if thermal or voltage violations are seen, the maximum permissible Provisional Interconnection before violations is identified. For voltage violations caused by reactive power deficiency at the POI, voltage upgrades are identified.

The Provisional Interconnection request should meet the transient stability criteria stated in Section 3.2. If the addition of the GIR causes any violations, the maximum permissible Provisional Interconnection Service before violations is identified.

3.5 Contingency Analysis

The transmission system on which steady state contingency analysis is run includes the WECC designated areas 70 and 73.

The transient stability analysis is performed for the following worst-case contingencies shown in Table 1.

Table 1 – Transient Stability Contingencies

| Ref. No. | Fault Location | Fault Category | Outage(s) | Clearing Time (Cycles) |
|----------|---------------------|----------------|---|------------------------|
| 1 | - | P0 | Flatrun | - |
| 2 | Goose Creek 345 kV | P1 | May Valley - Goose Creek 345 kV ckt 1 | 4 |
| 3 | Goose Creek 345 kV | P1 | Goose Creek - Canal Crossing 345 kV ckt 1 | 4 |
| 4 | Goose Creek 345 kV | P1 | Goose Creek - Shortgrass 345 kV ckt 1 | 4 |
| 5 | Goose Creek 345 kV | P1 | Goose Creek - Cheyenne Ridge 345 kV ckt 1 Cheyenne Ridge Wind Generation | 4 |
| 6 | Goose Creek 345 kV | P1 | PI-2024-12 Generation | 4 |
| 7 | Daniels Park 345 kV | P4 | Daniels Park - Missile Site 345 kV ckt 1 Daniels Pak 345 kV Cap Bank | 12 |
| 8 | Pronghorn 345 kV | P4 | Pronghorn - Rush Creek 345 kV ckt Rush Creek Wind Generation Daniels Park 345 kV Cap Bank | 12 |

| Ref. No. | Fault Location | Fault Category | Outage(s) | Clearing Time (Cycles) |
|----------|-----------------------|----------------|--|------------------------|
| 9 | Canal Crossing 345 kV | P4 | Goose Creek - Canal Crossing 345 kV ckt 1 Goose Creek - Canal Crossing 345 kV ckt 2 Canal Crossing 345 kV Cap Bank | 12 |

3.6 Study Area

The Eastern Colorado study area includes WECC designated zones 706. As described in Section 3.11 of the BPM, the study pocket East is comprised of the eastern Colorado transmission system with major generation injecting into Pawnee, Beaver Creek and Missile Site substations.

4.0 Base Case Modeling Assumptions

The study was performed using the 2024HS3 WECC base case that has been modified to represent a 2026 heavy summer loading conditions. The following planned transmission projects are modeled in the Base Case:

- Canal Crossing 345 kV switching station
- Fort Saint Vrain 345 kV substation
- Goose Creek 345 kV switching station
- May Valley 345 kV switching station
- Sand 230 kV substation
- Kestrel 230 kV substation
- Coyote 230 kV substation
- Poder 115 kV substation
- Metro Water 115 kV substation
- Pintail 115 kV substation
- DCPL Tap 115 kV substation
- Carl Tap 69 kV substation

The following additional changes were made to the Intermountain Regional Electric Co-Op (CORE) model in the Base Case:

- Citadel 115 kV substation
- Spring Valley 115 kV substation
- Deer Trail 115 kV substation

The Base Case model includes higher-queued and existing PSCo and Affected System generation resources.

4.1 Benchmark Case Modeling

The Benchmark Case was created from the Base Case described in Section 4.0 by changing the study pocket generation dispatch to reflect heavy generation in the Eastern Colorado study pocket. This was accomplished by adopting the stressed generation dispatch given in Table 2.

**Table 2 – Generation Dispatch Used to Create the Eastern Colorado Benchmark Case
(MW is Gross Capacity)**

| Bus No. | Bus Name | Base kV | ID | Status | Pgen (MW) | Pmax (MW) |
|---------|----------|---------|----|--------|-----------|-----------|
| 70310 | PAWNEE | 22 | C1 | 1 | 523.60 | 526.00 |
| 70314 | MANCHEF1 | 16 | G1 | 1 | 118.40 | 131.50 |
| 70315 | MANCHEF2 | 16 | G2 | 1 | 117.90 | 131.00 |

| Bus No. | Bus Name | Base kV | ID | Status | Pgen (MW) | Pmax (MW) |
|--------------|--------------|---------|----|--------|-----------|-----------|
| 70721 | SPRNGCAN1_W1 | 0.57 | W1 | 1 | 51.80 | 64.80 |
| 70710 | PTZLOGN1 | 34.5 | W1 | 1 | 160.80 | 201.00 |
| 70712 | PTZLOGN2 | 34.5 | W2 | 1 | 96.00 | 120.00 |
| 70713 | PTZLOGN3 | 34.5 | W3 | 1 | 63.60 | 79.50 |
| 70714 | PTZLOGN4 | 34.5 | W4 | 1 | 140.00 | 175.00 |
| 70715 | SPRNGCAN2_W2 | 0.69 | W2 | 1 | 50.20 | 62.70 |
| 70733 | CHEYRGE_W1 | 0.69 | W1 | 1 | 43.20 | 54.00 |
| 70736 | CHEYRGE_W2 | 0.69 | W2 | 1 | 88.00 | 110.00 |
| 70739 | CHEYRGW_W1 | 0.69 | W1 | 1 | 109.12 | 136.40 |
| 70742 | CHEYRGW_W2 | 0.69 | W2 | 1 | 105.60 | 132.00 |
| 70670 | CEDARPT_W1 | 0.69 | W1 | 1 | 99.36 | 124.20 |
| 70671 | CEDARPT_W2 | 0.69 | W2 | 1 | 100.80 | 126.00 |
| 70767 | RUSHCK1_W1 | 0.69 | W1 | 1 | 161.12 | 201.40 |
| 70770 | RUSHCK1_W2 | 0.69 | W2 | 1 | 130.32 | 162.90 |
| 70771 | RUSHCK2_W3 | 0.69 | W3 | 1 | 166.40 | 208.00 |
| 70635 | LIMON1_W | 34.5 | W1 | 1 | 160.80 | 201.00 |
| 70636 | LIMON2_W | 34.5 | W2 | 1 | 160.80 | 201.00 |
| 70637 | LIMON3_W | 34.5 | W3 | 1 | 160.80 | 201.00 |
| 70753 | BRONCO_W1 | 0.69 | W1 | 1 | 117.28 | 146.64 |
| 70749 | BRONCO_W2 | 0.69 | W2 | 1 | 128.96 | 161.18 |
| 70443 | ARRIBA_W1 | 0.69 | W1 | 1 | 80.08 | 100.05 |
| 70442 | ARRIBA_W2 | 0.69 | W2 | 1 | 80.08 | 100.05 |
| Total | | | | | 3215.02 | 3857.32 |

4.2 Study Case Modeling

A Study Case was created from the Benchmark Case by turning on the PI-2024-12 generation. The additional 438 MW output from PI-2024-12 was balanced against PSCo generation outside of the Eastern Colorado study pocket.

4.3 Short-Circuit Modeling

This request is for the interconnection of a 450 MW Wind Generating Facility (PI-2024-12) to the Goose Creek 345 kV switching station. The output will not exceed 438 MW at the POI.

This project assumes the use of one hundred (100) Vestas V163 4.5 MW wind turbine generators (WTGs) rated at 5.3 MVA operating at +/-0.826 pf for PI-2024-12. Each of the WTGs is connected to a collector transformer, 0.72/34.5 kV, rated at 5.3 MVA. Three 345/34.5/13.8 kV main GSU

transformers rated at 113/150/187 MVA step the voltage up from the collector transformer voltage to the POI voltage. The fault current from the interconnection assumed to be shared equally between the three GSUs. An approximately 6-mile-long generation tie line interconnects the project to the Goose Creek 345 kV switching station.

All connected generating facilities were assumed capable of producing maximum fault current. As such, all generation was modeled at full capacity, whether Network Resource Interconnection Service (NRIS) or ERIS is requested. Generation is modeled as a separate generating resource in PSS CAPE software and included at full capacity in the short-circuit study, regardless of any limitations to the output that would be imposed otherwise.

5.0 Provisional Interconnection Service Analysis

5.1 Voltage and Reactive Power Capability Evaluation

Per Section 4.1.1.1 of the BPM, the following voltage regulation and reactive power capability requirements are applicable to non-synchronous generators:

- Xcel Energy's OATT requires all non-synchronous generator Interconnection Customers to provide dynamic reactive power within the power factor range of 0.95 leading to 0.95 lagging at the high side of the generator substation. Furthermore, Xcel Energy requires every Generating Facility to have dynamic voltage control capability to assist in maintaining the POI voltage schedule specified by the Transmission Operator.
- It is the responsibility of the Interconnection Customer to determine the type (switched shunt capacitors and/or switched shunt reactors, etc.), the size (MVar), and the locations (on the Interconnection Customer's facility) of any additional static reactive power compensation needed within the generating plant in order to have adequate reactive capability to meet the +/- 0.95 power factor at the high side of the main step-up transformer.
- It is the responsibility of the Interconnection Customer to compensate their generation tie-line to ensure minimal reactive power flow under no load conditions.

Per Section 4.1.1.2 in the BPM, the following voltage regulation and reactive power capability requirements are applicable to synchronous generators:

- Xcel Energy's OATT requires all synchronous Generator Interconnection Customers to provide dynamic reactive power within the power factor range of 0.95 leading to 0.95 lagging at the POI.
- The reactive power analysis performed in this report is an indicator of the reactive power requirements at the POI and the capability of the generator to meet those requirements. The Interconnection Customer is required to demonstrate to the satisfaction of PSCo Transmission Operations prior to the commercial in-service date of the generating plant that it can safely and reliably operate within the required power factor and the regulating voltage of the POI.

All proposed reactive devices in customer provided models are switched favourably to provide appropriate reactive compensation in each test, therefore identified deficiencies are in addition to any proposed reactive compensation.

All the summary tables representing the GIR's Voltage and Reactive Power Capability tests adhere to the following color formatting representing the different aspects of the tests:

- Values highlighted in red indicate a failed reactive power requirement.
- Voltages outside the range of 0.95 p.u. to 1.05 p.u. are highlighted in yellow to provide additional information.

The PI-2024-12 GIR is modeled as follows:

Wind Generator 1: Pmax = 144 MW, Pmin = 0 MW, Qmax = 81.6 MVar, Qmin= -70.4 MVar

Wind Generator 2: Pmax = 162 MW, Pmin = 0 MW, Qmax = 91.8 MVar, Qmin= -79.2 MVar

Wind Generator 3: Pmax = 144 MW, Pmin = 0 MW, Qmax = 81.6 MVar, Qmin= -70.4 MVar

The summary for the Voltage and Reactive Power Capability Evaluation for PI-2024-12 is:

- The GIR is capable of meeting ± 0.95 pf at the high side of the main step-up transformer while maintaining a normal operating voltage at the POI. Note during the lagging test, each generator terminal bus exceeded 1.05 p.u. voltage.
- The GIR is capable of meeting ± 0.95 pf at its terminals while meeting the interconnection service request.
- The reactive power exchange and voltage change across the gen-tie are acceptable under no load conditions.

The Voltage and Reactive Power Capability tests performed for PI-2024-12 are summarized in Table 3.

Table 3 – Reactive Capability Evaluation for PI-2024-12

| Generator 1 Terminals | | | | | Generator 2 Terminals | | | | | High Side of Main Transformer | | | |
|-----------------------|----------------|----------------|----------------|-------------|-----------------------|----------------|----------------|----------------|-------------|-------------------------------|-------------|-------------|---------|
| Pgen (MW) | Qgen (Mvar) | Qmax (Mvar) | Qmin (Mvar) | V (p.u.) | Pgen (MW) | Qgen (Mvar) | Qmax (Mvar) | Qmin (Mvar) | V (p.u.) | P (MW) | Q (Mvar) | V (p.u.) | PF |
| 144.00 | 76.80 | 81.60 | -70.40 | 1.080 | 162.00 | 86.40 | 91.80 | -79.20 | 1.080 | 436.90 | 154.90 | 1.030 | 0.9425 |
| 144.00 | -23.90 | 81.60 | -70.40 | 0.971 | 162.00 | -26.80 | 91.80 | -79.20 | 0.974 | 437.40 | -155.40 | 0.990 | -0.9423 |
| 0.00 | -19.00 | 81.60 | -70.40 | 0.990 | 0.00 | -21.40 | 91.80 | -79.20 | 0.977 | -3.40 | -31.00 | 1.025 | -0.1090 |
| | | | | | Generator 3 Terminals | | | | | POI | | | |
| | | | | | Pgen (MW) | Qgen (Mvar) | Qmax (Mvar) | Qmin (Mvar) | V (p.u.) | P (MW) | Q (Mvar) | V (p.u.) | PF |
| | | | | | 144.00 | 76.80 | 81.60 | -70.40 | 1.080 | 436.50 | 153.80 | 1.024 | 0.9432 |
| | | | | | 144.00 | -23.90 | 81.60 | -70.40 | 0.971 | 436.90 | -157.30 | 0.993 | -0.9409 |
| | | | | | 0.00 | -19.00 | 81.60 | -70.40 | 0.978 | -3.40 | -25.90 | 1.025 | -0.1302 |

5.2 Steady State Analysis

Contingency analysis was performed on the East study pocket Study Case.

The power flow analysis showed that the category P1 contingencies: Missile Site – Pronghorn 345 kV was divergent in the Study Case. As described in Section 7.4 of the BPM, single contingency issues should be mitigated using redispatch. Therefore, to resolve the divergence without requiring network upgrades or curtailment of the Study GIR's output, PSCo units located near the Study GIR were re-dispatched until the diverged contingency was resolved. The change in output of the units was balanced against PSCo generation outside of the Eastern Colorado study pocket. The following single and multiple contingency analyses are conducted with the dispatch presented in the last column of Table 4.

Table 4 – Generation Dispatch to Resolve the Diverged P1 Contingency

| Generator Bus Number | Generator Name | ID | Initial Pgen (MW) | Modified Pgen (MW) |
|-----------------------------|-----------------------|-----------|--------------------------|---------------------------|
| 70767 | RUSHCK1_W1 | W1 | 161.10 | 0.00 |

- No thermal or voltage violations were observed during system intact analysis.
- Results of the single contingency analysis on the Study Case are shown in Table 5. Single contingency analysis showed no voltage violations attributable to PI-2024-12.
- Results of the multiple contingency analysis on the Study Case are shown in Table 6. Multiple contingency analysis showed no voltage violations attributable to PI-2024-12.
 - Note one P7 contingency was divergent as shown in Table 7. The contingency was divergent in both the Benchmark and Study Cases, so it is not attributable to the study GIR. Per TPL-001-5, multiple contingency overloads are mitigated using system adjustments, including generation redispatch (includes GIRs under study) and/or operator actions. None of the multiple contingency overloads are attributed to the study GIRs.

All single contingency overloads identified in Table 5 are alleviated through generation redispatch.

Table 5 – East Pocket - Single Contingency Overloads

| Ref. No. | Monitored Facility | Contingency Name | kVs | Areas | Rate Cont (MVA) | Benchmark Case Loading (%) | Study Case Loading (%) | Loading Difference (%) |
|----------|--|-----------------------------------|---------|-------|-----------------|----------------------------|------------------------|------------------------|
| 1 | Story (73192) - Pawnee (70311) 230 kV CKT 1 | Smokey Hill - Missile Site #7081 | 230 | 73/70 | 581 | 123.89 | 139.25 | 15.36 |
| 2 | Fort Lupton (70192) - Pawnee (70311) 230 kV CKT 1 | Smokey Hill - Missile Site #7081 | 230 | 70 | 478 | 103.56 | 110.62 | 7.06 |
| 3 | EFMORGTP (73305) - FMWEST (73379) 115 kV CKT 1 | Smokey Hill - Missile Site #7081 | 115 | 73 | 121 | 98.64 | 101.83 | 3.19 |
| 4 | Smoky Hill 345/230 kV (70599/70396) Transformer T4 | Smokey Hill - Harvest Mile 230 kV | 345/230 | 70 | 560 | 99.58 | 100.98 | 1.40 |
| 5 | Smoky Hill 345/230 kV (70599/70396) Transformer T5 | Smokey Hill - Harvest Mile 230 kV | 345/230 | 70 | 560 | 99.58 | 100.98 | 1.40 |

Table 6 – East Pocket - Multiple Contingency Overloads

| Ref. No. | Monitored Facility | Contingency Name | kVs | Areas | Rate Cont (MVA) | Benchmark Case Loading (%) | Study Case Loading (%) | Loading Difference (%) |
|----------|--|--|-----|-------|-----------------|----------------------------|------------------------|------------------------|
| 1 | Story (73192) - Pawnee (70311) 230 kV CKT 1 | P7_136: Pawnee - Brick Center 230 kV CKT 1 and Smoky Hill - Missile Site 345 kV CKT 1 | 230 | 73/70 | 589 | 154.80 | 175.44 | 20.64 |
| 2 | Buckley2 (70046) - Smoky Hill (70396) 230 kV CKT 1 | BF_064c: Greenwood Bus Tie | 230 | 70 | 478 | 148.86 | 150.37 | 1.51 |
| 3 | Fort Lupton (70192) - Pawnee (70311) 230 kV CKT 1 | P7_136: Pawnee - Brick Center 230 kV CKT 1 and Smoky Hill - Missile Site 345 kV CKT 1 | 230 | 70 | 478 | 122.54 | 132.45 | 9.91 |
| 4 | Buckley2 (70046) - Tollgate (70491) 230 kV CKT 1 | BF_064c: Greenwood Bus Tie | 230 | 70 | 554 | 128.45 | 129.74 | 1.29 |
| 5 | Clark (70112) - Jordan (70241) 230 kV CKT 1 | P7_58: Daniels Park - Prairie 230 kV CKT 1 and 2 | 230 | 70 | 364 | 120.35 | 121.87 | 1.52 |
| 6 | Jewell2 (70239) - Leetsdale (70260) 230 kV CKT 1 | BF_064c: Greenwood Bus Tie | 230 | 70 | 478 | 118.26 | 119.81 | 1.55 |
| 7 | Smoky Hill (70599) - Missile Site (70624) 345 kV CKT 1 | P7_61: Daniels Park - Missile Site 230 kV CKT 1 and Daniels Park - Missile Site 345 kV CKT 1 | 345 | 70 | 1775 | 106.83 | 116.27 | 9.44 |
| 8 | Jewell2 (70239) - Tollgate (70491) 230 kV CKT 1 | BF_064c: Greenwood Bus Tie | 230 | 70 | 555 | 111.50 | 112.81 | 1.31 |
| 9 | Daniels Park (70139) - Missile Site (70623) 230 kV CKT 1 | P7_136: Pawnee - Brick Center 230 kV CKT 1 and Smoky Hill - Missile Site 345 kV CKT 1 | 230 | 70 | 789 | 95.65 | 104.29 | 8.64 |

| Ref. No. | Monitored Facility | Contingency Name | kVs | Areas | Rate Cont (MVA) | Benchmark Case Loading (%) | Study Case Loading (%) | Loading Difference (%) |
|----------|--|---|-----|-------|-----------------|----------------------------|------------------------|------------------------|
| 10 | EFMORGTP (73305) - FMWEST (73379) 115 kV CKT 1 | P7_136: Pawnee - Brick Center 230 kV CKT 1 and Smoky Hill - Missile Site 345 kV CKT 1 | 115 | 73 | 133 | 98.66 | 103.36 | 4.70 |

Table 7 – Diverged P7 Contingencies

| Diverged Contingency | Contingency Description | BM Case | Study Case |
|----------------------|--|----------|------------|
| P7_135 | Daniels Park - Missile Site 345 kV circuit 1 Smoky Hill - Missile Site 345 kV circuit 1 | Diverged | Diverged |

5.3 Transient Stability Results

The following results were obtained for all disturbances analysed except for the P4 contingency shown in Ref. No. 9 in Table 8.:

- ✓ No machines lost synchronism with the system.
- ✓ No transient voltage drop violations were observed.
- ✓ Machine rotor angles displayed positive damping.

The results of the contingency analysis are shown in Table 8. The transient stability plots are shown in Appendix A in Section 10.0 of this report.

The response observed during the category P4 contingency shown in Ref. No. 9 in Table 8 may require either a Remedial Action Scheme (RAS) or Corrective Action Plan (CAP). Mitigation has not been determined at this time.

Table 8 – Transient Stability Analysis Results

| Ref. No. | Fault Location | Fault Category | Outage(s) | Clearing Time (Cycles) | Post-Fault Voltage Recovery | Angular Stability |
|----------|-----------------------|----------------|--|------------------------|-----------------------------|-------------------|
| 1 | - | P0 | Flatrun | - | Stable | Stable |
| 2 | Goose Creek 345 kV | P1 | May Valley - Goose Creek 345 kV ckt 1 | 4 | Stable | Stable |
| 3 | Goose Creek 345 kV | P1 | Goose Creek - Canal Crossing 345 kV ckt 1 | 4 | Stable | Stable |
| 4 | Goose Creek 345 kV | P1 | Goose Creek - Shortgrass 345 kV ckt 1 | 4 | Stable | Stable |
| 5 | Goose Creek 345 kV | P1 | Goose Creek - Cheyenne Ridge 345 kV ckt 1 Cheyenne Ridge Wind Generation | 4 | Stable | Stable |
| 6 | Goose Creek 345 kV | P1 | PI-2024-12 Generation | 4 | Stable | Stable |
| 7 | Daniels Park 345 kV | P4 | Daniels Park - Missile Site 345 kV ckt 1 Daniels Pak 345 kV Cap Bank | 12 | Stable | Stable |
| 8 | Pronghorn 345 kV | P4 | Pronghorn - Rush Creek 345 kV ckt Rush Creek Wind Generation | 12 | Stable | Stable |
| 9 | Canal Crossing 345 kV | P4 | Goose Creek - Canal Crossing 345 kV ckt 1 Goose Creek - Canal Crossing 345 kV ckt 2 Canal Crossing 345 kV Cap Bank | 12 | Unsatisfactory | Unsatisfactory |

5.4 Short-Circuit and Breaker Duty Analysis Results

The fault currents at the POI for three-phase and phase-to-ground faults can be found in Table 9 below, along with the Thevenin impedance at the POI. Both the base case and the case with the GIR added are shown.

Table 9 – Short-Circuit Parameters at PI-2024-12 POI (Goose Creek 345 kV switching station)

| | Before the PI Addition | After the PI Addition |
|-------------------------------|---------------------------|---------------------------|
| Three Phase | | |
| Three Phase Current | 7800 A | 6910 A |
| Positive Sequence Impedance | $2.15398 + j22.5968$ ohms | $2.15398 + j22.5968$ ohms |
| Negative Sequence Impedance | $2.18224 + j22.5892$ ohms | $2.18224 + j22.5892$ ohms |
| Zero Sequence Impedance | $2.04038 + j19.4567$ ohms | $0.91418 + j9.37496$ ohms |
| Phase-to-Ground | | |
| Single Line to Ground Current | 17690 A | 20580 A |
| Positive Sequence Impedance | $4.15880 + j48.2318$ ohms | $4.16772 + j48.2258$ ohms |
| Negative Sequence Impedance | $4.34649 + j48.1785$ ohms | $4.35504 + j48.1722$ ohms |
| Zero Sequence Impedance | $2.04038 + j19.4567$ ohms | $0.91418 + j9.37496$ ohms |

A breaker duty study on the PSCo transmission system did not identify any circuit breakers that became over-dutied because of adding the wind generation PI-2024-12.

5.5 Affected Systems

No Affected Systems were identified.

5.6 Summary of Provisional Interconnection Analysis

All system intact and single contingency thermal violations were alleviated through generation redispatch, therefore, the maximum allowable output of the GIR without requiring any additional System Network Upgrades is 438 MW.

6.0 Cost Estimates

The total estimated cost of the required upgrades for PI-2024-12 to interconnect for Provisional Interconnection Service at the Goose Creek 345 kV switching station is **\$8.822 million**. Note that cost estimates for system Network Upgrades on Affected Systems would not be provided by PSCo.

- Cost of Transmission Provider's Interconnection Facilities (TPIF) is \$5.456 million (Table 10)
- Cost of Station Network Upgrades is \$3.366 million (Table 11)
- Cost of System Network Upgrades is \$0

The list of improvements required to accommodate the Provisional Interconnection of PI-2024-12 are given in Table 10, and Table 11.

Table 10 – Transmission Provider's Interconnection Facilities

| Element | Description | Cost Est. (Million) |
|---|---|------------------------|
| PSCo's Goose Creek 345 kV switching station | Interconnection of 5RSC-2024-16 (PI-2024-12) at the Goose Creek 345 kV switching station. The new equipment includes: <ul style="list-style-type: none"> • (1) 345 kV single bay dead end structure • (1) 345 kV 3-phase arrester • (1) 345 kV 3000 A line disconnect switch • (3) 345 kV 1-phase CTs for metering • (3) 345 kV 1-phase CCVTs • Yard expansion including grading, ground grid, surfacing and fencing • Dual fiber communication equipment • Associated electrical equipment, bus, wiring and grounding • Associated foundations and structures • Associated transmission line communications, fiber, relaying and testing | \$5.206 |
| PSCo's Goose Creek 345 kV switching station | Transmission Provider's dead-end structure at the Point of Change of Ownership (PCO) outside the switching station fence line and transmission line into new switching station from the PCO. Dead end structure, single span, 3 conductors, insulators, hardware, jumpers and labor. | \$0.250 |
| Total Cost Estimate for Interconnection Customer-Funded, PSCo-Owned Interconnection Facilities | | \$5.456 |

Table 11 – Station Network Upgrades

| Element | Description | Cost Est. (Million) |
|---|--|--------------------------------|
| PSCo's Goose Creek 345 kV switching station | Interconnection of 5RSC-2024-12 (PI-2024-12) at the Goose Creek 345 kV switching station. The new equipment includes: <ul style="list-style-type: none"> • (1) 345 kV dead end structure • (1) 345 kV 3000 A SF6 circuit breaker • (1) 345 kV 3000 A disconnect switch • Associated electrical equipment, bus, wiring and grounding • Associated foundations and structures | \$2.958 |
| PSCo's Goose Creek 345 kV switching station | Install required communication in the EEE at the Goose Creek 345 kV switching station | \$0.358 |
| PSCo's Goose Creek 345 kV switching station | Siting and Land Rights permitting | \$0.050 |
| Total Cost Estimate for PSCo-Funded, PSCo-Owned Interconnection Facilities | | \$3.366 |

PSCo has developed cost estimates for Interconnection Facilities and Network/Infrastructure Upgrades required for the interconnection of PI-2024-12 for Provisional Interconnection Service. The estimated costs provided in this report are based upon the following assumptions:

- The estimated costs are in 2024 dollars with escalation and contingencies applied.
- Allowances for Funds Used During Construction (AFUDC) is not included.
- The estimated costs include all applicable labor and overheads associated with the siting, engineering, design, and construction of these new PSCo facilities.
- The estimated costs do not include the cost for any Customer owned equipment and associated design and engineering.
- Labor is estimated for straight time only—no overtime included.
- PSCo (or its Contractor) will perform all construction, wiring, testing, and commissioning for PSCo owned and maintained facilities.

The customer requirements include:

- Customer will install two (2) redundant fiber optic circuits (one primary circuit with a redundant backup) into the Transmission Provider's substation as part of its interconnection facilities construction scope.
- Power Quality Metering (PQM) will be required on the Customer's generation tie-line terminating into the POI.

- The Customer will be required to design, procure, install, own, operate and maintain a Load Frequency/Automated Generation Control (LF/AGC) RTU at their Customer substation. PSCo will be provided with indications, readings, and data from the LF/AGC RTU.

The Interconnection Customer will comply with the most current version of the *Interconnection Guidelines for Transmission Interconnected Producer-Owned Generation Greater Than 20 MW*, as amended from time to time, and available at: [Interconnection | Transmission | Corporate | Xcel Energy](#)

6.1 Schedule

This section provides proposed milestones for the interconnection of PI-2024-12 to the Transmission Provider's Transmission System. The customer requested a back-feed date (In-Service Date for Transmission Provider Interconnection Facilities and Station Network Upgrades required for interconnection) for the Provisional Interconnection of 9/20/2025. This is not attainable by the Transmission Provider, based upon the current schedule developed for this interconnection request. The Transmission Provider proposes the milestones provided below in Table 12.

Table 12 – Proposed Milestones for PI-2024-12

| Milestone | Responsible Party | Estimated Completion Date |
|--|--|---------------------------|
| LGIA Execution | Interconnection Customer and Transmission Provider | December 2024 |
| In-Service Date for Transmission Provider Interconnection Facilities and Station Network Upgrades required for interconnection | Transmission Provider | April 1, 2026 |
| In-Service Date & Energization of Interconnection Customer's Interconnection Facilities | Interconnection Customer | April 1, 2026 |
| Initial Synchronization Date | Interconnection Customer | May 1, 2026 |
| Begin trial operation & testing | Interconnection Customer and Transmission Provider | July 1, 2026 |
| Commercial Operation Date | Interconnection Customer | October 1, 2026 |



Some schedule elements are outside of the Transmission Provider's control and could impact the overall schedule. The following schedule assumptions provide the basis for the schedule milestones:

- Construction permitting (if required) for new facilities will be completed within 12 months of LGIA execution.
- The Transmission Provider is currently experiencing continued increases to material lead times which could impact the schedule milestones. The schedule milestones are based upon material lead times known at this time.
- Availability of line outages to interconnect new facilities to the transmission system.

7.0 Summary of Provisional Interconnection Service Analysis

The total estimated cost of the PSCo transmission system improvements required for PI-2024-12 to qualify for Provisional Interconnection Service would be \$8.822 million.

The initial maximum permissible output of PI-2024-12 Generating Facility is 438 MW. The maximum permissible output of the Generating Facility in the PLGIA will be reviewed quarterly and updated if there are changes to system conditions compared to the system conditions previously used to determine the maximum permissible output.

Security: PI-2024-12 is a request for ERIS. For ERIS requests, security shall estimate the risk associated with the Network Upgrades and the Interconnection Facilities and is assumed to be a minimum of \$5 million.


The Provisional Interconnection Service in and of itself does not convey transmission service.

8.0 Contingent Facilities









Contingent Facilities identified for PI-2024-12 include the TPIF and Station Network Upgrades identified in Table 10 and Table 11, respectively.

Page 31 of 32









10.0 Appendices

| | |
|--|---|
| <p>Appendix A: Transient Stability Plots</p> | <p> PI-2024-12_Transient Stability Plots.pdf</p> |
|--|---|









PI-2024-12_Study_East_flatrun



















PI-2024-12_Study_East_MayV-GooseCrk-1_345kV




PI-2024-12_Study_East_GooseCrk-CanalXing-1_345kV









PI-2024-12_Study_East_BF_9

